# **Ø2.85m**CENTRE DISCHARGE SILO

EB Equipment Ltd Redbrook Barnsley South Yorkshire S75 1HR

## **FEATURES & BENEFITS**

- Designed in accordance with Euro-code norms, taking structural, wind, snow loads and terrain into consideration
- Manufactured from EB Equipment's unique blend of polyester glass reinforced plastic
- Corrosion resistant and UV stabilised for long life
- Top access hatch incorporating ventilation fitted as standard
- Smooth interior with a 60° cone angle allowing consistent flow of content
- Single piece cone and body construction eliminates seams, joints and bolted sections
- Superior thermal insulation values when compared to steel silos
- Supporting steel work is fully welded from structural hollow section and hot dip galvanised
- Fill pipe includes long radius bends to allow smooth filing with minimum product damage
- Ventilation pipe maintains internal ambient temperature



Optional Inspection Hatch



Optional colours available in **ANY** RAL/BS colour, see examples below:













Colours are for references purposes only and may not be accurately reproduced in printing



Example shown is a 30m<sup>3</sup> Centre Discharge Silo. All sizes are approximate and subject to change.

# Ø2.85m **CENTRE DISCHARGE SILO**

SILO Part No:	VOLUME	HEIGHT	INTERNAL DIAMETER	INSIDE LEG	DISCHARGE HEIGHT	CAPACITY		MINIMUM CONCRETE
						Tonnes 560 kg/ m³	Tonnes 693 kg/ m³	BASE SIZE
2215 S	15m³	5.4m	2.85m	1.94m	0.8m	8.4T	10.4T	4.0 x 4.0 x 0.3m
2220 S	20m³	6.2m				11.2T	13.9T	
2225 S	25m³	7.0m				14.0T	17.3T	
2230 S	30m³	7.8m				16.8T	20.8T	
2235 S	35m³	8.6m				19.6T	24.3T	
2240 S	40m³	9.2m				22.4T	27.8T	

Bespoke sizes available on request, please speak to a member of our team.

#### **CONCRETE BASE DETAILS**

The material should be concrete with a minimum compressive strength of 35N/mm<sup>2</sup>.

The concrete shall be re-enforced with an A393 mesh, placed 50mm max from the bottom of the concrete.

The upper 200mm MUST NOT incorporate any re-enforcing mesh.

#### **GETTING THE SILO READY TO USE**

- 1. It is the clients responsibility to construct a concrete base which must be fully cured prior to delivery.
- 2. EB silos are delivered and installed by vehicles equipped with hydraulic tipping gears which erect the silo onto the concrete base.
- 3. Once the silo is erected, the driver will drill the concrete base and bolt the silo into position using through bolt/ anchor.

### **DELIVERY VEHICLE / ACCESSIBILITY**

Check for overhead cables, ensure adequate clearance to enable silo erection.



Height: 4.8m, Width: 2.9m, Weight: 22 tonnes approx.



V001 - 02/01/2019

